

## Controller Information

Controller Name	Beacon
Software Build Version	1.0.4
Controller IP Address	192.168.84.149
OpenFlow port	6633
Connection Mode	TCP
OpenFlow Version(s)	1.0

## Test Configuration


Test Type	Latency
Test Mode	Normal
Flow Measurement By	Packet-out
Test Duration (sec)	5
# of iteration(s)	5
Iteration Delay (sec)	5
Warmup Time (sec)	5
# of Switch(es)	2

## Switch Group - 1 Switch

OpenFlow Version	1.0	# of Switch(es)	2
Start MAC Address	00:00:00:00:00:01	# of Port(s)	2
Traffic Profile	TCP	Packet Length	64
Selected Modifier	Source MAC	# of Flow(s)	64
# of Flow Table(s)	4	# of Group Table(s)	1
# of Meter Table(s)	1	Max. Entries per Flow Table	65,536
Switch Buffers Size	0		
Switch Capabilities	Flow Stats,Table Stats,Port Stats		

Performance Chart

Total OF Connection Time (ms)	1016.778	Average OF Connection Time (ms)	1016.778
-------------------------------	----------	---------------------------------	----------





S.No	Iteration	Latency (ms)
1	1	8.9164
2	2	9.4402
3	3	9.3609
4	4	9.4135
5	5	9.4920

Trial Version  
Not intended for commercial use